

ADDENDUM #1

JURUPA UNIFIED SCHOOL DISTRICT

**Bid No. 21-22-14TEIB
RHS Audio Upgrade Project**

5/2/2022:

TO ALL BIDDERS:

The following changes, omissions, and/or additions to the Project Manual and/or Drawings shall apply to proposals made for and to the execution of the various parts of the work affected thereby, and all other conditions shall remain the same.

All parties of interest shall take careful note of the addendum so that the proper allowances may be made in strict accordance with the Addendum.

*****Bidder shall acknowledge receipt of this addendum in the space provided on the Bid Form. Failure to do so may subject Bidder disqualification.***

In case of conflict between Drawings, bid documents and this addendum, this addendum shall govern.

ITEM #1

Specifications:

Specifications are hereby incorporated into the bid documents.

RHS Audio Upgrades

Room	A	B	C	D	E	F	Proj Type
101	C	Y	Y	Y	Y	N	CP-X25LWN
102	C	Y	Y	Y	Y	N	CP-X2530WN
103	C	Y	Y	Y	Y	N	CP-X2521WN
104	C	Y	Y	Y	Y	N	EX3551
105	C	Y	Y	Y	Y	N	CP-X25LWN
106	C	Y	Y	Y	Y	N	CP-X2542WN
107	C	Y	Y	Y	Y	N	CP-X2521WN
108	C	Y	Y	Y	Y	N	EX3551
109	C	Y	Y	Y	Y	N	CP-X2542WN
110	C	Y	Y	Y	Y	N	CP-X2530WN
111	C	Y	Y	Y	Y	N	CP-X2530WN
112	C	Y	Y	Y	Y	N	CP-X2542WN
201	C	Y	Y	Y	Y	N	CP-X2542WN
202	C	Y	Y	Y	Y	N	CP-X2542WN
203	C	Y	Y	Y	Y	N	CP-EX3051WN
204	C	Y	Y	Y	Y	N	CP-X2530WN
205	C	Y	Y	Y	Y	N	CP-X2542WN
206	C	Y	Y	Y	Y	N	CP-X2530WN
207	C	Y	Y	Y	Y	N	CP-X2541WN
208	C	Y	Y	Y	Y	N	SHARP NOTEVISION
301	C	Y	Y	Y	Y	N	CP-EX3051WN
302	C	Y	Y	Y	Y	N	CP-EX3551WN
303	C	Y	Y	Y	Y	N	CP-X2542WN
304	C	Y	Y	Y	Y	N	SHARP NOTEVISION
305	C	Y	Y	Y	Y	N	MC-EX3551
306	C	Y	Y	Y	Y	N	CP-X2530WN
307	C	Y	Y	Y	Y	N	CP-EX3051WN
401	C	Y	Y	Y	Y	N	CP-X2542WN
402	C	Y	Y	Y	Y	N	CP-EX3051WN
403	C	Y	Y	Y	Y	N	EX3551
501	C	Y	Y	Y	Y	N	CP-X2542WN
502	C	Y	Y	Y	Y	N	CP-X2542WN
503	C	Y	Y	Y	Y	N	CP-X2541WN
600	C	N	N	N	N	N	CP-X2542WN
601	C	N	N	N	Y	1 SPK	CP-X2541WN
602	C	N	N	N	N	N	cp-x2510
603	C	Y	Y	Y	Y	N	CP-X2011
604	C	Y	Y	Y	Y	N	CP-X2530WN
605	C	N	Y	Y	N	N	CP-X25LWN
606	N/A						
607	OFFICE						
608	N/A						
609	C	N	N	N	N	N	CP-X2521WN
800	N/A						
801	N/A						
802	N/A						
1001	N/A						
1002	W	Y	Y	Y	Y	N	685W
1003a	N/A						
1003b	N/A						
1004	W	Y	Y	Y	Y	N	685W
1006	W	Y	Y	Y	Y	N	685W
1010	W	Y	Y	Y	Y	N	685W
1011	W	Y	Y	Y	Y	N	685W
1012	W	Y	Y	Y	Y	N	685W
1013	W	Y	Y	Y	Y	N	685W
Café	N/A						
1100	C	N	N	N	Y	Y	CP-X2542WN

A=Wall or Ceiling mount
 B=Remove Extron Amp/switcher
 C=Remove Extron MLC
 D=Remove Extron AV faceplates
 E=Install Stewart Amp, connect spk,SB
 F=Install Speakers

OFFSET

OFFSET

VISION

ml

VISION

1201	W	Y	Y	Y	Y	N	685W
1202	W	Y	Y	Y	Y	N	685W
1203	W	Y	Y	Y	Y	N	685W
1204	W	Y	Y	Y	Y	N	685W
1205	W	Y	Y	Y	Y	N	685W
1206	N/A						
1207	W	Y	Y	Y	Y	N	685W
1208	N/A						
1209	W	Y	Y	Y	Y	N	685W
1210	W	Y	Y	Y	Y	N	685W
1211	W	Y	Y	Y	Y	N	685W
1213	W	Y	Y	Y	Y	N	685W
1215	W	Y	Y	Y	Y	N	685W
1216	W	Y	Y	Y	Y	N	685W
1217	W	Y	Y	Y	Y	N	685W
1218	W	Y	Y	Y	Y	N	685W
1219	W	Y	Y	Y	Y	N	685W
1220	W	Y	Y	Y	Y	N	685W
1601	C	Y	Y	Y	Y	N	CP-X2541WN
1602	C	Y	Y	Y	Y	N	CP-X25LWN
1800	N/A						
M0	N/A						
M1	N/A						
M2	N/A						
M3	N/A						
M4	N/A						
M5	N/A						
M6	N/A						
M7	N/A						

Column A indicates if the existing projector is a ceiling or wall mount.

Column B indicates if contractor is to remove existing Extron Polevault system (PVS204SA), bottom and side panels of the Polevault casing, RS232 cable to projector, and power to the switcher.

Column C indicates if contractor is to remove existing Extron controller (MLC 104 IP Plus), cabling to the controller from the switcher. Provide and install double gang blank on device backbox.

Column D indicates if contractor is to remove existing existing Extron AV faceplates, typically below the controller. Remove cabling to the controller from the switcher. Provide and install (1) single gang blank plate onto both of the device backboxes.

Column E indicates if the contractor is to provide and install a Stewart Audio AV30MX-2, mounting it to the bottom of the existing Extron top plate or above the ceiling by providing and installing a Stewart Audio AV-BRACKET. Contractor to connect existing speaker cabling to amplifier.

Column F indicates if the contractor is to provide and install (2) OWI IC6TBBC speakers, backcan, and tile mount kit. Provide and install WestPenn 77292 20/2 STP cable from the speaker to the amplifier. Quantity of "1" indicates the same requirements, but with one speaker.

All active electronic devices shall be turned over to the district, including power supplies.

Typical Extron controller:



Typical AV faceplates



Extron plate with polevault equipment/cabling removed. Front view.



Extron plate with polevault equipment/cabling removed. Rear view.

